



CB&I
12005 Ford Road, Suite 600
Dallas, Texas 75234
Tel: 972.773.8400
Fax: 972.773.8401
www.CBI.com

August 4, 2016

Mr. Dwight Russell, P.E.
Municipal Solid Waste Permits Section – MC 124
Texas Commission on Environmental Quality
P.O. Box 13087
Austin, Texas 78711-3087

Re: Pescadito Environmental Resource Center - Webb County
Municipal Solid Waste (MSW) Permit Application No. 2374
Permit Application Supplement
Tracking Nos. 14669041(19666994); CN603835489/RN106119639

Dear Mr. Russell;

CB&I Environmental and Infrastructure, Inc. (CB&I) is providing the attached information to supplement the referenced permit application which was declared technically complete on March 11, 2016. We are providing these changes in order to include a flexible membrane liner (FML) component in the Final Cover System over cells that receive Class 1 industrial wastes even though the previous Alternative Final Cover System was approved for use over Class 1 wastes. This revision has required slight changes to various portions of the application and they are included as attachments to this letter. As noted throughout the submitted pages, we are currently designating all cells at the facility to be able to accept Class 1 wastes; however PERC reserves the right to modify the permit in the future to remove the Class 1 waste designation from specific cells and revert to the previously approved Alternative Final Cover System over such cells.

Our submittal is formatted as follows:

- Attachment A contains a revised signature page from the Part 1 form and a revised pages 1, 9 and 12 of the Master Table of Contents.
- Attachment B contains the original version of the changed pages.
- Attachment C contains a redline version of the changed pages.
- Attachment D contains three (3) copies of the original changed pages found in Attachment B.

The following table describes the changed sections and how they should be inserted into the application.

File Name	Changed Pages
Master Table of Contents	Page 1, 9, 12
Part III, Attachment III-B – General Facility Design	Cover page, Table of Contents and page 6
Part III, Attachment III-C, Appendix III-C.2 – Facility Surface Water Drainage Drawings	Cover page, Table of Contents and Drawing III-C.2-7
Part III, Attachment III-D, Appendix III-D.3 – Landfill Design and Details	Cover page, Table of Contents and Drawings III-D.3-2, 3, 4, 6 and 11
Part III, Attachment III-D, Appendix III-D.5 – Geotechnical Analyses	Cover page, Table of Contents, Appendix Fly Sheet and new Appendix III-D.5-7
Part III, Attachment III-D, Appendix III-D.8-3 – Alternative Final Cover with FML Demonstration – new section	Cover page, Table of Contents and new section III-D.8-3
Part III, Attachment III-D, Appendix III-D.9 - Final Cover Quality Control Plan	Cover page, Table of Contents and Pages 1-5 (entire section)
Part III, Attachment III-H – Closure Plan	Cover page, Table of Contents and Page 4
Part III, Attachment III-J - Cost Estimates for Closure and Post-Closure Care	Cover page, Table of Contents and page 1; Appendix III-J.1 Cover, pages 1 and 2
Part IV - Site Operating Plan	Cover page, Table of Contents and Page 57

The information provided in this submittal has also been sent to the Laredo Public Library and uploaded to the web site at www.pescaditoerc.com. We trust this information is clear and complete; however, should you need additional information, please let us know.

Sincerely,
CB&I Environmental and Infrastructure, Inc.
TBPE Firm F-5650



Michael W. Oden, P.E.
Project Manager

Attachments

- A - Part 1 Form Signature Page, Table of Contents Revisions
- B – Original Replacement pages
- C – Redline/Strikeout version of changed pages
- D – Three copies of changed pages (TCEQ only)

CC: Mr. Carlos Y. Benavides III
Mr. William W. Thompson
Mr. Geoffrey S. Connor

Attachment A
to August 2016 Supplement Letter (MSW 2374)

Part I Form Signature Page and
Page 1, 9 and 12 of Master Table of Contents

Signature Page

I, Carlos Y. Benavides, III, Manager
(Site Operator (Permittee/Registrant)'s Authorized Signatory) (Title)

certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Signature: CY Benavides III Date: Aug 4 2016

TO BE COMPLETED BY THE OPERATOR IF THE APPLICATION IS SIGNED BY AN AUTHORIZED REPRESENTATIVE FOR THE OPERATOR

I, _____, hereby designate _____
(Print or Type Operator Name) (Print or Type Representative Name)

as my representative and hereby authorize said representative to sign any application, submit additional information as may be requested by the Commission; and/or appear for me at any hearing or before the Texas Commission on Environmental Quality in conjunction with this request for a Texas Water Code or Texas Solid Waste Disposal Act permit. I further understand that I am responsible for the contents of this application, for oral statements given by my authorized representative in support of the application, and for compliance with the terms and conditions of any permit which might be issued based upon this application.

Printed or Typed Name of Operator or Principal Executive Officer

Signature

SUBSCRIBED AND SWORN to before me by the said _____

On this 4th day of August, 2016

My commission expires on the 11 day of March, 2018

Norma V. Valdez
Notary Public in and for

Webb County, Texas

(Note: Application Must Bear Signature & Seal of Notary Public)



Pescadito Environmental Resource Center
MSW No. 2374
Master Table of Contents

PART I


1.0 REQUIREMENTS OF §305.45 [330.59(a)]3
 1.1 Form TCEQ-0650 [305.45(a)(1)-(5)]3
 1.2 Maps [305.45(a)(6)]3
 1.3 Permits or Construction Approvals [305.4(a)(7)]3
 1.4 Supplementary Technical Report [305.45(a)(8)]4
 1.4.1 General Description of the Facilities4
 1.4.2 Volumes, Rates and Characteristics of Wastes11
 1.4.3 Other Information12
 2.0 FACILITY LOCATION [330.59(b)]14
 3.0 MAPS [330.59(c)]15
 4.0 PROPERTY OWNER INFORMATION [330.59(d)]20
 4.1 Legal Description20
 4.2 Property Owner Affidavit20
 5.0 LEGAL AUTHORITY [330.59(e)]21
 6.0 EVIDENCE OF COMPETENCY [330.59(f)]22
 7.0 APPOINTMENTS [330.59(g)]23
 8.0 APPLICATION FEE [330.59 (h)]24

PART I Figures

Figure 1 General Location Map
 Figure 2 Detailed Location Map
 Figure 3 Land Ownership Map
 Figure 4 Boundary Survey (Sheets 1 to 4 of 4)

PART I Attachments

Attachment A Legal Description
 Attachment B Certificate of Incorporation
 Attachment C Payment Demonstration



8-4-2016

This document is released for the purpose of permitting only under the authority of Michael W. Oden, P.E. #67165. It is not to be used for bidding or construction. Texas Registered Engineering Firm F-5650.

Pescadito Environmental Resource Center
MSW No. 2374
Master Table of Contents - continued

Attachment III-D, Appendix III-D.5 APPENDICES

- Appendix III-D.5-1 Summary of Geotechnical Design Parameters
- Appendix III-D.5-2 Slope Stability Analyses
- Appendix III-D.5-3 Foundation Bearing Capacity Analyses
- Appendix III-D.5-4 Landfill Foundation Settlement, Waste Settlement, and Soil Liner Strain Analyses
- Appendix III-D.5-5 Final Cover Stability Analysis
- Appendix III-D.5-6 Sideslope Liner Runout Analyses (with and without an Anchor Trench)
- Appendix III-D.5-7 Final Cover Stability Analysis with Flexible Membrane Liner

Attachment III-D, Appendix III-D.6 – Leachate and Contaminated Water Plan

1.0	Introduction.....	1
2.0	Overview of Leachate.....	2
3.0	Overview of Leachate Collection System.....	3
3.1	Drainage Layer.....	3
3.2	Leachate Collection Pipes in Chimney.....	3
3.3	Leachate Collection Sumps.....	4
3.4	Leachate Pump and Riser System.....	5
3.5	Conveyance.....	5
3.6	Leachate Storage.....	5
4.0	Analysis of Leachate Collection System Adequacy.....	7
4.1	Pipe Strength Analysis.....	7
4.2	Geocomposite and Geotextile Flow Capacity Analysis.....	8
4.3	Determination of Peak Leachate Generation Rates.....	9
5.0	Operations.....	14
5.1	Leachate and Contaminated Water Minimization.....	14
5.2	Leachate and Contaminated Water Plan.....	14
5.3	Leachate Treatment and Disposal.....	15
5.4	Monitoring and Maintenance.....	15
5.5	Recordkeeping.....	16

Attachment A to Appendix III-D.6: Contaminated Water/Leachate Collection System Design Analysis

1. Loads on the Leachate Collection System
2. Ring Deflection of Leachate Pipe
3. Structural Capacity of the Leachate Collection System
4. Compressed Thickness and Hydraulic Conductivity of the Geonet
5. HELP Model Analysis
6. Leachate Collection System Flow Rates
7. Geotextile Permittivity
8. Leachate Collection System Design
9. Leachate Tank Size

Attachment B to Appendix III-D.6: HELP Model Outputs

1. Summary Table of HELP Model Runs
2. Open Conditions
 - a. Leachate Collection System Scenario A
 - b. Leachate Collection System Scenario B

Pescadito Environmental Resource Center
MSW No. 2374
Master Table of Contents - continued

9.0	GEOTEXTILES.....	46
9.1	Materials	46
9.2	Delivery.....	46
9.3	Quality Control Testing	46
9.4	Installation.....	47
	9.4.1 Surface Preparation.....	47
	9.4.2 Deployment.....	47
	9.4.3 Repairs	47
9.5	Documentation.....	48
10.0	PROTECTIVE COVER.....	49
10.1	Materials	49
10.2	Quality Assurance Testing	49
10.3	Cover Placement	50
11.0	LINERS CONSTRUCTED BELOW THE SEASONAL HIGH WATER TABLE.....	52
11.1	Seasonal High Water Elevations.....	52
11.2	Poorly Permeable	52
11.3	Liner Design.....	52
12.0	DOCUMENTATION	53
12.1	SLER Markers	54
12.2	Interim Status Report	54
12.3	Report Acceptance.....	54

Attachment III-D , Appendix III-D.7-1 - Poorly Permeable Demonstration

1.0	Subsurface Water Occurrence, Flow Characteristics, and Potentiometric Heads.....	1
2.0	General Excavation and Excavation Dewatering Considerations.....	3
3.0	Liner Tensile Strain Design for Uplift.....	4
4.0	Site-Specific Liner Uplift and Tensile Strain Calculations.....	5
4.1	Volume of water required to distort liner to allowable tensile strain.....	5
4.2	Subsurface water flow available to distort liner.....	5
4.3	Time required to distort liner up to the allowable tensile strain.....	6

Attachment III-D, Appendix III-D.8 – Alternate Final Cover Demonstration

1.0	Introduction.....	1
2.0	Alternate Final Cover System Design.....	2
3.0	Equivalency Demonstration requirements	3
4.0	Soil loss due to erosion	4
5.0	Help model.....	5
5.1	Input Parameters	5
6.0	Alternative Final Cover Quality Control Plan	10
7.0	Conclusion	11

Attachments to Appendix III-D.8

Attachment III-D.8-1: HELP 3.07 Output

Attachment III-D.8-2: References

Attachment III-D.8-3: Alternate Final Cover Demonstration with Flexible Membrane Liner

Pescadito Environmental Resource Center
MSW No. 2374
Master Table of Contents

PART I

1.0 REQUIREMENTS OF §305.45 [330.59(a)]3
 1.1 Form TCEQ-0650 [305.45(a)(1)-(5)]3
 1.2 Maps [305.45(a)(6)]3
 1.3 Permits or Construction Approvals [305.4(a)(7)]3
 1.4 Supplementary Technical Report [305.45(a)(8)]4
 1.4.1 General Description of the Facilities4
 1.4.2 Volumes, Rates and Characteristics of Wastes11
 1.4.3 Other Information12
 2.0 FACILITY LOCATION [330.59(b)]14
 3.0 MAPS [330.59(c)]15
 4.0 PROPERTY OWNER INFORMATION [330.59(d)]20
 4.1 Legal Description20
 4.2 Property Owner Affidavit20
 5.0 LEGAL AUTHORITY [330.59(e)]21
 6.0 EVIDENCE OF COMPETENCY [330.59(f)]22
 7.0 APPOINTMENTS [330.59(g)]23
 8.0 APPLICATION FEE [330.59 (h)]24

PART I Figures

Figure 1 General Location Map
 Figure 2 Detailed Location Map
 Figure 3 Land Ownership Map
 Figure 4 Boundary Survey (Sheets 1 to 4 of 4)

PART I Attachments

Attachment A Legal Description
 Attachment B Certificate of Incorporation
 Attachment C Payment Demonstration

This document is released for the purpose of permitting only under the authority of Michael W. Oden, P.E. #67165. It is not to be used for bidding or construction. Texas Registered Engineering Firm F-5650.

Pescadito Environmental Resource Center
MSW No. 2374
Master Table of Contents - continued

Attachment III-D, Appendix III-D.5 APPENDICES

- Appendix III-D.5-1 Summary of Geotechnical Design Parameters
- Appendix III-D.5-2 Slope Stability Analyses
- Appendix III-D.5-3 Foundation Bearing Capacity Analyses
- Appendix III-D.5-4 Landfill Foundation Settlement, Waste Settlement, and Soil Liner Strain Analyses
- Appendix III-D.5-5 Final Cover Stability Analysis
- Appendix III-D.5-6 Sideslope Liner Runout Analyses (with and without an Anchor Trench)
- Appendix III-D.5-7 Final Cover Stability Analysis with Flexible Membrane Liner

Attachment III-D, Appendix III-D.6 – Leachate and Contaminated Water Plan

1.0	Introduction.....	1
2.0	Overview of Leachate.....	2
3.0	Overview of Leachate Collection System.....	3
3.1	Drainage Layer.....	3
3.2	Leachate Collection Pipes in Chimney	3
3.3	Leachate Collection Sumps.....	4
3.4	Leachate Pump and Riser System.....	5
3.5	Conveyance.....	5
3.6	Leachate Storage.....	5
4.0	Analysis of Leachate Collection System Adequacy	7
4.1	Pipe Strength Analysis.....	7
4.2	Geocomposite and Geotextile Flow Capacity Analysis.....	8
4.3	Determination of Peak Leachate Generation Rates	9
5.0	Operations.....	14
5.1	Leachate and Contaminated Water Minimization.....	14
5.2	Leachate and Contaminated Water Plan	14
5.3	Leachate Treatment and Disposal	15
5.4	Monitoring and Maintenance.....	15
5.5	Recordkeeping	16

Attachment A to Appendix III-D.6: Contaminated Water/Leachate Collection System Design Analysis

1. Loads on the Leachate Collection System
2. Ring Deflection of Leachate Pipe
3. Structural Capacity of the Leachate Collection System
4. Compressed Thickness and Hydraulic Conductivity of the Geonet
5. Help Model Analysis
6. Leachate Collection System Flow Rates
7. Geotextile Permittivity
8. Leachate Collection System Design
9. Leachate Tank Size

Attachment B to Appendix III-D.6: HELP Model Outputs

1. Summary Table of HELP Model Runs
2. Open Conditions
 - a. Leachate Collection System Scenario A
 - b. Leachate Collection System Scenario B

Pescadito Environmental Resource Center
MSW No. 2374
Master Table of Contents - continued

9.0	GEOTEXTILES.....	46
9.1	Materials	46
9.2	Delivery.....	46
9.3	Quality Control Testing	46
9.4	Installation.....	47
	9.4.1 Surface Preparation.....	47
	9.4.2 Deployment.....	47
	9.4.3 Repairs	47
9.5	Documentation.....	48
10.0	PROTECTIVE COVER.....	49
10.1	Materials	49
10.2	Quality Assurance Testing	49
10.3	Cover Placement	50
11.0	LINERS CONSTRUCTED BELOW THE SEASONAL HIGH WATER TABLE.....	52
11.1	Seasonal High Water Elevations.....	52
11.2	Poorly Permeable	52
11.3	Liner Design.....	52
12.0	DOCUMENTATION	53
12.1	SLER Markers	54
12.2	Interim Status Report	54
12.3	Report Acceptance.....	54

Attachment III-D , Appendix III-D.7-1 - Poorly Permeable Demonstration

1.0	Subsurface Water Occurrence, Flow Characteristics, and Potentiometric Heads.....	1
2.0	General Excavation and Excavation Dewatering Considerations.....	3
3.0	Liner Tensile Strain Design for Uplift	4
4.0	Site-Specific Liner Uplift and Tensile Strain Calculations.....	5
4.1	Volume of water required to distort liner to allowable tensile strain.....	5
4.2	Subsurface water flow available to distort liner.....	5
4.3	Time required to distort liner up to the allowable tensile strain.....	6

Attachment III-D, Appendix III-D.8 – Alternate Final Cover Demonstration

1.0	Introduction.....	1
2.0	Alternate Final Cover System Design.....	2
3.0	Equivalency Demonstration requirements	3
4.0	Soil loss due to erosion	4
5.0	Help model.....	5
5.1	Input Parameters	5
6.0	Alternative Final Cover Quality Control Plan	10
7.0	Conclusion	11

Attachments to Appendix III-D.8

Attachment III-D.8-1: HELP 3.07 Output

Attachment III-D.8-2: References

Attachment III-D.8-3: Alternate Final Cover Demonstration with Flexible Membrane Liner