

Pescadito Environmental Resource Center
MSW No. 2374
Master Table of Contents

PART I

1.0 REQUIREMENTS OF §305.45 [330.59(a)]3
 1.1 Form TCEQ-0650 [305.45(a)(1)-(5)]3
 1.2 Maps [305.45(a)(6)]3
 1.3 Permits or Construction Approvals [305.4(a)(7)]3
 1.4 Supplementary Technical Report [305.45(a)(8)]4
 1.4.1 General Description of the Facilities4
 1.4.2 Volumes, Rates and Characteristics of Wastes11
 1.4.3 Other Information12
 2.0 FACILITY LOCATION [330.59(b)]14
 3.0 MAPS [330.59(c)]15
 4.0 PROPERTY OWNER INFORMATION [330.59(d)]20
 4.1 Legal Description20
 4.2 Property Owner Affidavit20
 5.0 LEGAL AUTHORITY [330.59(e)]21
 6.0 EVIDENCE OF COMPETENCY [330.59(f)]22
 7.0 APPOINTMENTS [330.59(g)]23
 8.0 APPLICATION FEE [330.59 (h)]24

PART I Figures

- Figure 1 General Location Map
- Figure 2 Detailed Location Map
- Figure 3 Land Ownership Map
- Figure 4 Boundary Survey (Sheets 1 to 4 of 4)

PART I Attachments

- Attachment A Legal Description
- Attachment B Certificate of Incorporation
- Attachment C Payment Demonstration

9-18-2015



This document is released for the purpose of permitting only under the authority of Michael W. Oden, P.E. #67165. It is not to be used for bidding or construction. Texas Registered Engineering Firm F-5650.

PART II

1.0 EXISTING CONDITIONS SUMMARY – [330.61(a)].....	5
1.1 Soils and Geology.....	5
1.2 Groundwater.....	5
1.3 Site Size and Topography.....	6
1.4 Rainfall, Hydrology and Storm Water Runoff.....	7
1.5 Floodplains.....	7
1.6 Threatened and Endangered Species.....	8
1.7 Land Use.....	8
1.8 Oil and Gas Production.....	8
2.0 WASTE ACCEPTANCE PLAN [330.61(b)].....	10
2.1 General.....	10
2.1.1 Type of Facility and Wastes to be Accepted.....	10
2.2 Sources and Characteristics of Waste.....	12
2.3 Quantity of Waste.....	13
3.0 GENERAL LOCATION MAPS [330.61(c)].....	15
4.0 FACILITY LAYOUT MAPS [330.61(d)].....	17
5.0 GENERAL TOPOGRAPHIC MAPS [330.61(e)].....	18
6.0 AERIAL PHOTOGRAPH [330.61(f)].....	19
7.0 LAND-USE MAP [330.61(g)].....	20
8.0 IMPACT ON SURROUNDING AREA [330.61(h)].....	21
8.1 Potential Impact on Human Health.....	21
8.2 Potential Impact on the Environment.....	23
8.3 Compatibility with the Surrounding Area.....	23
9.0 TRANSPORTATION [330.61(i)].....	26
10.0 GENERAL GEOLOGY AND SOILS STATEMENT [330.61(j)].....	28
10.1 General Geology [330.61(j)(1)].....	28
10.2 General Soils [330.61(j)(1)].....	28
10.3 Fault Areas [330.61(j)(2) and 330.555].....	28
10.4 Seismic Impact Zones [330.61(j)(3) and 330.557].....	29
10.5 Unstable Areas [330.61(j)(4) and 330.559].....	30
11.0 GROUNDWATER AND SURFACE WATER [330.61(k)].....	32
11.1 Groundwater [330.61(k)(1)].....	32
11.2 Surface Water [330.61(k)(2)].....	33
12.0 ABANDONED OIL AND WATER WELLS [330.61(l)].....	35
13.0 FLOODPLAINS AND WETLANDS STATEMENT [330.61(m)].....	36
14.0 ENDANGERED OR THREATENED SPECIES [330.61(n)].....	38
15.0 TEXAS HISTORICAL COMMISSION REVIEW [330.61(o)].....	39
16.0 COUNCIL OF GOVERNMENTS - LOCAL GOVERNMENT REVIEW [330.61 (p)].....	40
17.0 AIR POLLUTION CONTROL [330.371].....	41
18.0 GENERAL OPERATIONAL CONSIDERATIONS [330.15].....	42

PART II Figures

Figure 1	General Location Map
Figure 2	Wind Rose Map
Figure 3	Facility Layout Map
Figure 4	Operations Area Layout Map
Figure 5	Future Operations Area Layout Map
Figure 6	General Topographic Map
Figure 7	Aerial Photograph
Figure 8	Land Use Map
Figure 9	Supplemental Land Use Map
Figure 10	USGS Seismic Hazard Map
Figure 11	Flood Insurance Rate Map

PART II Attachments

Attachment A	T&E Species and Wetlands Assessment
Attachment B	TxDOT Coordination
Attachment C	Texas Historical Commission Review
Attachment D	Cultural Resources Review
Attachment E	Local Agency Coordination
Attachment F	Federal Aviation Administration Coordination
Attachment G	100-Year Floodplain Coordination
Attachment H	TPDES Certification
Attachment I	Oil Well Affidavit

PART III

Attachment III-A – Site Development Plan Narrative

1.0	INTRODUCTION	1
1.1	Geology and Soil Conditions	1
1.2	Drainage	2
1.3	Land Use and Zoning	3
1.4	Adequacy of Access Roads and Highways	4
2.0	GENERAL FACILITY DESIGN	6
3.0	FACILITY SURFACE WATER DRAINAGE DESIGN	7
4.0	WASTE MANAGEMENT UNIT DESIGN	8
5.0	GEOLOGY REPORT	9
6.0	GROUNDWATER MONITORING PLAN	10
7.0	LANDFILL GAS MANAGEMENT PLAN	11
8.0	CLOSURE PLAN	12
9.0	POST-CLOSURE CARE PLAN	13
10.0	COST ESTIMATES FOR CLOSURE AND POST-CLOSURE CARE	14

Attachment III-B – General Facility Design

1.0	FACILITY ACCESS	1
2.0	WASTE MOVEMENT	3
2.1	Waste Disposal	4
2.2	Class 1 Industrial Waste	6
2.3	Liquid Solidification	7
2.4	RACM	7
2.5	Large Item and Tire Storage Areas	7
2.6	Reusable Materials Staging Area	8
2.7	Citizen's Convenience Center	9
2.8	Leachate Storage Facility	9
3.0	SANITATION	10
3.1	Large Item and Tire Storage Areas	10
3.2	Reusable Materials Staging Area	10
3.3	Citizen's Convenience Center	10
3.4	Leachate Storage Facility	11
3.5	Liquid Solidification	11
3.6	General Information	11
4.0	ENDANGERED SPECIES PROTECTION	13

Attachment III-B, Appendix III-B.1 – General Facility Design Figures

III-B.1-1 Waste Flow Diagram.....	1
III-B.1-2 Waste Disposal, Processing and Storage Plan.....	2
III-B.1-3 Entrance Facilities.....	3
III-B.1-4 Convenience Center Details.....	4
III-B.1-5 Liquid Solidification Basin Plan and Details.....	5
III-B.1-6 Leachate Storage Details.....	6
III-B.1-7 Evaporation Pond Plan, Profiles and Details.....	7

Attachment III-C – Facility Surface Water Drainage Report

1.0 Introduction.....	1
-----------------------	---

Attachment III-C, Appendix III-C.1 Facility Surface Water Drainage Report Narrative

1.0 INTRODUCTION.....	1
2.0 DRAINAGE REVISIONS PRIOR TO LANDFILL FACILITY DEVELOPMENT.....	3
2.1 Pre-Development Conditions.....	3
2.2 Intermediate Conditions (Post-CLOMR Modifications).....	4
2.3 Key Conclusion of CLOMR.....	5
2.4 Incorporation of CLOMR Assumptions into Proposed Design.....	5
3.0 OBJECTIVES OF MODELING.....	7
4.0 OBJECTIVE 1.....	9
5.0 OBJECTIVE 2.....	12
5.1 Model Analysis Setup.....	12
5.2 Rainfall.....	12
5.3 Model Inputs.....	13
5.4 Post-Development Hydrologic Overview.....	14
5.5 Key Modeling Results for Landfill Stormwater Management Components.....	19
6.0 OBJECTIVE 3.....	21
7.0 OBJECTIVE 4.....	23

Attachment III-C, Appendix III-C.1, Attachment III-C.1-A Approved Conditional Letter of Map Revision

Attachment III-C, Appendix III-C.2 Facility Surface Water Drainage Drawings

III-C.2-1 Pre-Development Conditions – Regional Overview.....	1
III-C.2-2 Pre-Development Conditions – Facility and Immediate Surroundings.....	2
III-C.2-3 Intermediate Development Conditions – Regional Overview.....	3
III-C.2-4 Intermediate Development Conditions – Facility and Immediate Surroundings.....	4
III-C.2-5 Post-Development Conditions – Facility and Immediate Surroundings.....	5
III-C.2-6 Post-Development Stormwater Feature Overview.....	6
III-C.2-7 Terrace Berm, Downchute, and Perimeter Channel Details.....	7
III-C.2-8 Perimeter Channel Culvert Details.....	8
III-C.2-9 Perimeter Channel Drainage Profiles (A and B).....	9
III-C.2-10 Perimeter Channel Drainage Profiles (C, D, E and F).....	10
III-C.2-11 Detention Basin Plan, Profile and Details (1 of 2).....	11
III-C.2-12 Detention Basin Plan, Profile, and Details (2 of 2).....	12
III-C.2-13 Erosion Control Details.....	13

III-C.2-14	100-Year Floodplain Cross Section Plan View	14
III-C.2-15	100-Year Floodplain Cross Section Profile View	15

Attachment III-C, Appendix III-C.3 Drainage Analysis

III-C.3-1.	Rainfall Totals and Distributions
III-C.3-2.	Stormwater Management Features Delineation
III-C.3-3.	Runoff Curve Number Determination
III-C.3-4.	Subcatchment Lag Time
III-C.3-5.	Subcatchment Area Discharge Rates
III-C.3-6.	Terrace Bench Sizing
III-C.3-7.	Downchute Sizing
III-C.3-8.	Perimeter Channel Sizing
III-C.3-9.	Culvert Sizing
III-C.3-10.	South Detention Basin Sizing and Discharge Rates
III-C.3-A	Facility Stormwater Feature Delineation Figure

Attachment III-C, Appendix III-C.4 HydroCAD Model Outputs

III-C.4-1.	Regional Existing Conditions (Pre-CLOMR)
a.	Model Diagram
b.	100-year, 24-hour Results (Adjusted Rainfall – 9.5 inches)
c.	25-Year, 24-hour Results
III-C.4-2.	Regional Intermediate Conditions (Post-CLOMR)
a.	Model Diagram
b.	100-year, 24-hour Results (Adjusted Rainfall – 9.5 inches)
c.	25-Year, 24-hour Results
III-C.4-3.	Proposed Conditions (Post-Development)
a.	Model Diagrams
b.	Landfill Watershed A (typical of Watersheds C, E, G, I, K, M, and O)
i.	100-year, 24-hour (Adjusted Rainfall – 9.5 inches)
ii.	25-Year, 24-hour
c.	Landfill Watershed B (typical of Watersheds D, F, J, J, L, N, and P)
i.	100-year, 24-hour (Adjusted Rainfall – 9.5 inches)
ii.	25-Year, 24-hour
d.	Landfill Perimeter Ditch, Culvert, and Basin System
i.	100-year, 24-hour (Adjusted Rainfall – 9.5 inches)
ii.	25-Year, 24-hour
e.	Regional Stormwater Conditions
i.	100-year, 24-hour (Adjusted Rainfall – 9.5 inches)

Attachment III-C, Appendix III-C.5 Erosion Control Plan

1.0	INTRODUCTION.....	1
2.0	BEST MANAGEMENT PRACTICES	2
3.0	PHYSICAL EROSION CONTROL METHODS	3
4.0	EROSION CONTROL DURING CONSTRUCTION.....	5
5.0	INTERMEDIATE COVER CONSIDERATIONS	8
5.1	Stormwater Velocities along Intermediate Cover Surface	8
5.2	Intermediate Cover Erosion Loss Evaluation.....	8
5.3	Intermediate Cover Soil Stabilization and Vegetation Schedule.....	9
5.4	Intermediate Cover Inspection and Maintenance	10
6.0	EROSION CONTROL DURING FINAL LANDFORM CONDITIONS	11
6.1	Stormwater Velocities along Final Cover Surface	12
6.2	Final Cover Erosion Loss Evaluation.....	12
6.3	Final Cover Inspection and Maintenance	12

Attachment III-C, Appendix III-C.5 Attachments

III-C.5-A.	Flow Rate per Unit Area into Temporary Ditches and Swales
III-C.5-B.	Temporary Ditch Geometry
III-C.5-C.	Temporary Swale Geometry
III-C.5-D.	Sheet Flow Velocity on Intermediate Cover Slopes
III-C.5-E.	Soil Loss from Intermediate Cover Slopes
III-C.5-F.	Flow Rate per Unit Area from Final Cover Slopes
III-C.5-G.	Sheet Flow Velocity on Final Cover Slopes
III-C.5-H.	Soil Loss from Final Cover Slopes

Attachment III-D – Waste Management Unit Design

1.0	STORAGE AND TRANSFER UNITS.....	1
1.1	Liquid Solidification.....	1
1.2	Large Item and Tire Storage Areas.....	2
1.3	Reusable Materials Storage Area	3
1.4	Citizen's Convenience Center.....	3
1.5	Leachate Storage Facility	4
2.0	SURFACE IMPOUNDMENTS.....	5
3.0	LANDFILL UNITS.....	6
3.1	All Weather Operations.....	6
3.2	Landfilling Method.....	7
3.3	General Landfill Design and Site Life Calculations.....	7
3.4	Liner and Final Cover Quality Control Plans	8

Attachment III-D, Appendix III-D.1 – Site Layout

III-D.1-1	General Site Plan.....	1
III-D.1-2	Site Layout Plan	2
III-D.1-3	Excavation Plan	3
III-D.1-4	Landfill Completion Plan.....	4
III-D.1-5	Entrance Facilities Plan.....	5

III-D.1-6 Entrance Road Details.....	6
 <u>Attachment III-D, Appendix III-D.2 – Landfill Cross Sections</u>	
III-D.2-1 Section Layout Plan	1
III-D.2-2 North Unit, Landfill Section A-A’	2
III-D.2-3 North Unit, Landfill Section B-B’	3
III-D.2-4 South Unit, Landfill Section C-C’	4
III-D.2-5 South Unit, Landfill Section D-D’	5
III-D.2-6 Landfill Sections a-a” and b-b’	6
 <u>Attachment III-D, Appendix III-D.3 – Landfill Design and Details</u>	
III-D.3-1 Liner Plan.....	1
III-D.3-2 Liner Details.....	2
III-D.3-3 Liner Details.....	3
III-D.3-4 Liner Details.....	4
III-D.3-5 Leachate Collection System Plan.....	5
III-D.3-6 Leachate Collection Details	6
III-D.3-7 Leachate Collection Details	7
III-D.3-8 Leachate Collection Details	8
III-D.3-9 Leachate Storage Details.....	9
III-D.3-10 Final Cover Plan	10
III-D.3-11 Final Cover Details	11
 <u>Attachment III-D, Appendix III-D.4 – Landfill Operation and Site Life</u>	
1.0 SITE LIFE	1
2.0 LANDFILL CAPACITY.....	1
3.0 AIRSPACE UTILIZATION	1
Table III-D.4-1	2
 <u>Attachment III-D, Appendix III-D.5 – Geotechnical Analyses</u>	
Introduction	1
Organization of Report	1
Slope Stability Analyses.....	2
Short-Term and Long-Term Shear Strength Under Static Conditions	2
Critical Cross Section.....	2
Modeled Stability Scenarios.....	3
Slope Stability Results.....	3
Foundation Bearing Capacity Analyses	4
Landfill Foundation Settlement, Waste Settlement, and Soil Liner Strain Analyses	5
Foundation Settlement and Soil Liner Strain	5
Waste Settlement.....	5
Final Cover Stability Analysis.....	6
Sideslope Liner Runout Analyses (with and without an Anchor Trench).....	6

Attachment III-D, Appendix III-D.5 APPENDICES

- Appendix III-D.5-1 Summary of Geotechnical Design Parameters
- Appendix III-D.5-2 Slope Stability Analyses
- Appendix III-D.5-3 Foundation Bearing Capacity Analyses
- Appendix III-D.5-4 Landfill Foundation Settlement, Waste Settlement, and Soil Liner Strain Analyses
- Appendix III-D.5-5 Final Cover Stability Analysis
- Appendix III-D.5-6 Sideslope Liner Runout Analyses (with and without an Anchor Trench)

Attachment III-D, Appendix III-D.6 – Leachate and Contaminated Water Plan

1.0	Introduction	1
2.0	Overview of Leachate	2
3.0	Overview of Leachate Collection System	3
3.1	Drainage Layer	3
3.2	Leachate Collection Pipes in Chimney	3
3.3	Leachate Collection Sumps	4
3.4	Leachate Pump and Riser System	5
3.5	Conveyance	5
3.6	Leachate Storage	5
4.0	Analysis of Leachate Collection System Adequacy	7
4.1	Pipe Strength Analysis	7
4.2	Geocomposite and Geotextile Flow Capacity Analysis	8
4.3	Determination of Peak Leachate Generation Rates	9
5.0	Operations	14
5.1	Leachate and Contaminated Water Minimization	14
5.2	Leachate and Contaminated Water Plan	14
5.3	Leachate Treatment and Disposal	15
5.4	Monitoring and Maintenance	15
5.5	Recordkeeping	16

Attachment A to Appendix III-D.6: Contaminated Water/Leachate Collection System Design Analysis

1. Loads on the Leachate Collection System
2. Ring Deflection of Leachate Pipe
3. Structural Capacity of the Leachate Collection System
4. Compressed Thickness and Hydraulic Conductivity of the Geonet
5. Help Model Analysis
6. Leachate Collection System Flow Rates
7. Geotextile Permittivity
8. Leachate Collection System Design
9. Leachate Tank Size

Attachment B to Appendix III-D.6: HELP Model Outputs

1. Summary Table of HELP Model Runs
2. Open Conditions
 - a. Leachate Collection System Scenario A
 - b. Leachate Collection System Scenario B

- c. Leachate Collection System Scenario C
- d. Leachate Collection System Scenario D
- 3. Intermediate Conditions
- 4. Closed Conditions
- 5. Introduced Contaminated Water Analysis
 - a. Open Conditions – 20 Foot Waste Column
 - b. Intermediate Conditions – 50 Foot Waste Column
 - c. Intermediate Conditions – 100 Foot Waste Column

Attachment III-D, Appendix III-D.7 – Liner Quality Control Plan

1.0	INTRODUCTION.....	1
1.1	Liner	1
1.2	Definitions	2
1.3	Full Time Quality Assurance.....	5
2.0	SUBGRADE AND GENERAL FILL.....	6
2.1	General Fill.....	6
2.2	Surveying.....	6
3.0	COMPACTED SOIL LINER.....	8
3.1	Liner Soil Requirements.....	8
3.2	Preliminary Sampling and Testing Procedures.....	8
3.3	Soil Liner Sampling and Testing.....	9
	3.3.1 Density and Moisture Content.....	10
	3.3.2 Sieve Analysis and Atterberg Limits.....	10
	3.3.3 Coefficient of Permeability	11
	3.3.4 Thickness Verification.....	11
3.4	Construction of Compacted Soil Liners	11
	3.4.1 Placing and Compacting.....	11
	3.4.2 Liner Tie-Ins.....	13
	3.4.3 Surface Preparation and Maintenance.....	13
4.0	GEOMEMBRANE WITH BENTONITE (Option 1)	15
4.1	Manufacturing Quality Control (MQC) Testing.....	15
4.2	Delivery	16
4.3	Conformance Testing	16
4.4	BEGM Deployment.....	17
	4.4.1 Panel Placement	17
	4.4.2 Equipment	20
	4.4.3 Anchor Trenches	20
	4.4.4 Moisture Protection	21
4.5	Seams.....	21
	4.5.1 Panels.....	21
	4.5.2 Seaming.....	21
4.6	Repairs and Patching.....	22
4.7	Construction Quality Assurance.....	22
5.0	GEOMEMBRANE LINER (Option 2)	24
5.1	Manufacturing Quality Control (MQC) Testing.....	24

5.2	Delivery	24
5.3	Conformance Testing	25
5.4	GM Installation.....	25
	5.4.1 Continuous Inspection	25
	5.4.2 Subgrade.....	26
	5.4.3 Panel Placement	26
	5.4.4 Trial Welds	28
	5.4.5 Field Seaming.....	29
	5.4.5 Field Seam Evaluations	30
	5.5.1 Nondestructive Seam Testing.....	30
	5.5.2 Field Destructive Seam Sampling	32
	5.5.3 Field Destructive Seam Testing.....	33
5.6	Third Party Laboratory Seam Testing	34
	5.6.1 Samples	34
	5.6.2 Peel Test Requirements	34
	5.6.3 Shear Test Requirement	35
5.7	Failing Seam Tests	35
5.8	Repairs.....	35
	5.8.1 Repair Procedures.....	35
	5.8.2 Wrinkles	36
	5.8.3 Folded Material	37
	5.8.4 Bridging.....	37
5.9	GM Anchor Trench	37
5.10	GM Acceptance	37
6.0	DRAINAGE GEOCOMPOSITE	39
	6.1 Delivery	39
	6.2 Quality Control Testing.....	39
	6.3 Installation.....	39
	6.3.1 Surface Preparation	40
	6.3.2 Deployment	40
	6.4 Repairs.....	41
	6.5 Documentation	41
7.0	LEACHATE COLLECTION SYSTEM PIPING	42
	7.1 Delivery	42
	7.2 Quality Control.....	42
	7.3 Perforation Schedule – As shown on the plans	42
	7.4 Installation.....	42
	7.5 Documentation	43
8.0	DRAINAGE AGGREGATE.....	44
	8.1 Materials.....	44
	8.2 Quality Assurance	44
	8.2.1 Testing.....	44
	8.2.2 Construction Observations	45
	8.2.3 Documentation	45

9.0	GEOTEXTILES	46
9.1	Materials	46
9.2	Delivery	46
9.3	Quality Control Testing	46
9.4	Installation	47
	9.4.1 Surface Preparation	47
	9.4.2 Deployment	47
	9.4.3 Repairs	47
9.5	Documentation	48
10.0	PROTECTIVE COVER	49
10.1	Materials	49
10.2	Quality Assurance Testing	49
10.3	Cover Placement	50
11.0	LINERS CONSTRUCTED BELOW THE SEASONAL HIGH WATER TABLE	52
11.1	Seasonal High Water Elevations	52
11.2	Poorly Permeable	52
11.3	Liner Design	52
12.0	DOCUMENTATION	53
12.1	SLER Markers	54
12.2	Interim Status Report	54
12.3	Report Acceptance	54

Attachment III-D , Appendix III-D.7-1 - Poorly Permeable Demonstration

1.0	Subsurface Water Occurrence, Flow Characteristics, and Potentiometric Heads	1
2.0	General Excavation and Excavation Dewatering Considerations	3
3.0	Liner Tensile Strain Design for Uplift	4
4.0	Site-Specific Liner Uplift and Tensile Strain Calculations	5
4.1	Volume of water required to distort liner to allowable tensile strain.	5
4.2	Subsurface water flow available to distort liner	5
4.3	Time required to distort liner up to the allowable tensile strain.	6

Attachment III-D, Appendix III-D.8 – Alternate Final Cover Demonstration

1.0	Introduction	1
2.0	Alternate Final Cover System Design	2
3.0	Equivalency Demonstration requirements	3
4.0	Soil loss due to erosion	4
5.0	Help model	5
5.1	Input Parameters	5
6.0	Alternative Final Cover Quality Control Plan	10
7.0	Conclusion	11

Attachments to Appendix III-D.8

Attachment III-D.8-1: HELP 3.07 Output

Attachment III-D.8-2: References

Master Table of Contents - continued

Attachment III-D, Appendix III-D.9 – Final Cover Quality Control Plan

1.0	INTRODUCTION.....	1
2.0	FINAL COVER DESIGN.....	2
3.0	QUALITY ASSURANCE/QUALITY CONTROL.....	3
4.0	DOCUMENTATION.....	4

Attachment III-E - Geology

1.0	Introduction.....	1
2.0	Hydrogeologic Setting.....	4

Figure III-E.0-1 – Original and Revised Permit Boundaries.....12

Figure 2 – Generalized Conceptual Model of Site Hydrogeology 10

Attachment III-E , Appendix III-E.1 - Regional Geology and Hydrogeology

1.0	Regional Geology and Hydrogeology [(330.57(f), 330.63(e)(1))]	1
1.1	Introduction to Regional Geology.....	1
1.2	Geomorphology.....	1
1.3	Regional Geologic Framework [(330.63(e)(1))]	2
1.3.1	Mesozoic Development and Site Region Structural Setting—the Rio Grande Embayment....	6
1.3.2	The Cenozoic and transgressive and regressive stratigraphy [(330.63(e)(1)(B))]	7
1.3.3	Wilcox Growth Faulting [330.63(e), 330.555(b) and 330.559]	10
1.3.4	Carrizo, an aquifer in western Webb County.....	10
1.3.5	Bigford and Reklaw, equivalents.....	11
1.3.6	Queen City and El Pico --downdip equivalent of Weches, an aquifer then a confining zone	12
1.3.7	Laredo (elsewhere Sparta and Cook Mountain) with meaning for water.....	15
1.3.8	Yegua Formation (last of the Claiborne) and Jackson Group.....	16
1.4	Regional Geology Summary.....	19
2.0	Regional Hydrogeology.....	21
2.1	Groundwater Use in the Site Region.....	21
2.2	Precipitation, Evaporation and Recharge in the site region.....	21
2.3	Regional Aquifers.....	22
2.3.1	Carrizo Aquifer.....	23
2.3.2	Reklaw Confining Unit above the Carrizo.....	25
2.3.3	Queen City-Bigford.....	25
2.3.4	El Pico Confining Unit.....	26
2.3.5	Laredo.....	26
2.3.6	Yegua and Jackson Aquifer(s).....	28
2.4	Regional Hydrogeology Summary.....	30
3.0	Additional Geology Related Information.....	31
3.1	Area Water Wells.....	31
3.2	Area Oil and Gas Wells.....	31
3.3	Regional Seismicity and Induced Earthquakes.....	32
	Bibliography.....	35

Attachment III-E , Appendix III-E.1 - LIST OF TABLES

Table 1 – Stratigraphic Column	3
Table 2 – Hydrogeologic Properties.....	4
Table 3 – Are Water Wells.....	31

Attachment III-E , Appendix III-E.1 - LIST OF FIGURES

Figure 1 – Seismic Section Illustrating Lobo Slide.....	9
Figure 2 – Stratigraphic Dip Section.....	13
Figure 3 – Geophysical Log Section along Strike.....	14
Figure 3a – Location Map for Section J-J' and L-L' – From Ricoy 1976	14
Figure 4 - Geophysical Log Section along Dip.....	15
Figure 5 – Yegua Stratigraphic Section.....	18
Figure 6 – Generalized Stratigraphic Section.....	23
Figure 7 – Site Test Pit.....	29
Figure 8 – National Seismic Hazard Map	33
Figure 9 – Induced Seismicity Map.....	34

Attachment III-E, Appendix III-E.1 - LIST OF PLATES

Plate 1 – Geologic Map of the Region	39
Plate 2 - Hydrostratigraphic Section across Webb County	40
Plate 3 – Area Water Wells	41
Plate 4 - Area Oil and Gas Wells.....	42

Attachment III-E, Appendix III-E.2 - Subsurface Investigation Report

1.0 INTRODUCTION.....	1
2.0 FIELD EXPLORATION PROGRAM	1
2.1 SOIL BORING PLAN	2
2.2 PRELIMINARY ASSESSMENT (PHASES I AND II)	5
2.2.1 Soil Borings.....	5
2.2.2 Piezometers.....	6
2.3 SUBSURFACE INVESTIGATION (PHASE III)	6
2.3.1 Soil Borings and Piezometers.....	6
2.3.2 Borehole Geophysical Logging.....	8
2.4 SUBSURFACE INVESTIGATION (PHASE IV).....	9
3.0 DISCUSSION OF SITE STRATIGRAPHY.....	10
3.1 STRATUM I - RECENT-PLEISTOCENE SOILS	11
3.2 STRATUM II - HIGHLY WEATHERED EOCENE RESIDUUM	11
3.3 STRATUM III - WEATHERED EOCENE SOILS	12
3.4 STRATUM IV - RELATIVELY UNWEATHERED EOCENE SOILS	12
3.5 DISCUSSION OF SOIL CONDITIONS	12
4.0 GROUNDWATER DATA.....	14
4.1 PIEZOMETER INSTALLATION	14
4.2 WATER LEVEL MEASUREMENTS.....	16
4.2.1 Observations During Drilling.....	16
4.2.2 Water Levels Measured in Piezometers	17

4.2.3 Staff Gauge Measurements.....18
 4.2.4 Observations from Test Pits18

Attachment III-E, Appendix III-E.2 - LIST OF FIGURES

Figure 1 - Site Location Map
 Figure 2 - Boring/Test Pit Location Map
 Figure 3 - Cross Section Index Map
 Figure 4 - Interpretive Geologic Cross Section A-A'
 Figure 5 - Interpretive Geologic Cross Section B-B'
 Figure 6 - Interpretive Geologic Cross Section C-C'
 Figure 7 - Interpretive Geologic Cross Section D-D'
 Figure 8 - Interpretive Geologic Cross Section E-E'
 Figure 9 - Interpretive Geologic Cross Section F-F'
 Figure 10 - Interpretive Geologic Cross Section G-G'
 Figure 11 - Interpretive Geologic Cross Section H-H'
 Figure 12 - Interpretive Geologic Cross Section I-I'
 Figure 13 - Interpretive Geologic Cross Section J-J'
 Figure 14 - Conceptual Geologic Section
 Figure 15 - Piezometer/Staff Gauge Location Map
 Figure 16 - Combined Water Level Contour Map – 10/19/10
 Figure 17 - Combined Water Level Contour Map – 3/23/11
 Figure 18 - Combined Water Level Contour Map – 7/19-20/11
 Figure 19 - Combined Water Level Contour Map – 1/10/12
 Figure 20 - Shallow Water Level Contour Map with Staff Gauge Data – 7/19-20/11
 Figure 21 - Deep Water Level Contour Map – 7/19-20/11
 Figure 22 - Shallow Water Level Contour Map with Staff Gauge Data – 1/10/12
 Figure 23 - Deep Water Level Contour Map – 1/10/12

Attachment III-E, Appendix III-E.2 - LIST OF TABLES

Table 1 - Soil Boring/Test Pit/Staff Gauge Position Table
 Table 2 - Summary of Soil Boring/Test Pit Depths and Elevations
 Table 3 - Summary of Observations During Test Pit Installation
 Table 4 - Summary of Piezometer Construction Details and Screen Elevations
 Table 5 - Summary of Static Water Level Measurements – Piezometers
 Table 6 - Summary of Static Water Level Measurements – Staff Gauges

Attachment III-E, Appendix III-E.2 - LIST OF APPENDICES

Appendix A - TCEQ Approval Letter – April 21, 2011
 Appendix B - Boring Logs and Key to Terms and Symbols
 Appendix C - Borehole Geophysical Logs
 Appendix D - Piezometer Construction Diagrams
 Appendix E - State of Texas Well Reports

Attachment III-E, Appendix III-E.3 - Geotechnical Data Report

1.0 INTRODUCTION.....1
 2.0 FIELD EXPLORATION PROGRAM1
 2.1 STANDARD PENETRATION TEST (SPT).....1
 2.2 POCKET PENETROMETER2

3.0 LABORATORY TESTING	2
3.1 CLASSIFICATION TESTS	2
3.2 MOISTURE CONTENT TESTS	2
3.3 PERMEABILITY TESTS	3
4.0 STRATIGRAPHY AND SOIL PROPERTIES	3
4.1 GENERALIZED STRATIGRAPHY	3
4.2 SOIL PROPERTIES	4
5.0 CONCLUSIONS	4
6.0 REFERENCES	5

Attachment III-E, Appendix III-E.3 - LIST OF FIGURES

- Figure 1 - Site Location Map
- Figure 2 - Boring/Test Pit Location Map
- Figure 3 - Fence Diagram Index Map

Attachment III-E, Appendix III-E.3 - LIST OF APPENDICES

- APPENDIX A - Results of Soil Sample Analyses
- APPENDIX B - Hydraulic Conductivity Test Results
 - Figures B-1 Summary of Results
 - Figures B-2 through B-19 Hydraulic Conductivity Test Results (Detailed)
- APPENDIX C - Fence Diagnostics and Measured Soil Properties
 - Figures C-1 through C-10 Generalized Subsurface Fence Diagrams
 - Figures C-11 through C-14 Measured Soil Properties (by Stratum)

Attachment III-E, Appendix III-E.4 - Summary of Hydrogeologic Testing in Selected Piezometers

1.0 INTRODUCTION	1
2.0 SLUG TESTS	2
2.1 Setup	2
2.2 Falling Head Test and Rising Head Test	2
2.3 Slug Test Data Evaluation and Results	3
3.0 PUMP-DOWN TESTS	6
3.1 Setup	6
3.2 Pump-Down Recovery Test	6
3.3 Pump-Down Data Evaluation and Results	7
4.0 SUMMARY AND CONCLUSIONS	9
REFERENCES	10
TABLES	11

Attachment III-E, Appendix III-E.5 - Supplemental Subsurface Investigation Report – Phase V

1.0 INTRODUCTION	1
2.0 PREVIOUS INVESTIGATIONS – PHASES I-IV	2
2.1.1 RotoSonic Drilling Limitations	3
2.1.2 Subsurface Water Information	4
2.1.3 Hydrogeologic Testing of Phase III Piezometers	5
3.0 PHASE V INVESTIGATION	6
3.1.1 Field Investigation	6

Master Table of Contents - continued

3.1.2	Subsurface Water Observations.....	9
3.1.3	Piezometer Recovery Testing Results	11
3.1.4	Geotechnical Test Results	15
4.0	Yegua-Jackson Boundary Definition	17
5.0	Subsurface Water Quality Information	18
6.0	CONCLUSIONS	20

Attachment III-E, Appendix III-E.5 - List of Photos

Photo 1 - Test Pit 1 – January 2012.....	2
Photo 2 - Test Pit 1 – January 2015.....	3
Photo 3 - Grouting Boring B-52 – January 2015.....	7

Attachment III-E, Appendix III-E.5 - List of Tables

Table 1 - Piezometer Construction Summary.....	8
Table 2 – Permeability Results.....	12
Table 3 – Horizontal Permeability Calculations.....	15

Attachment III-E, Appendix III-E.5 - List of Figures

Figure 1 – Phase V Piezometers – Permeability Test Data	13
---	----

Attachment III-E, Appendix III-E.5, Attachments

- III-E.5-A - Figures
- III-E.5-B – Phase V Logs of Borings
- III-E.5-C - Photographs
- III-E.5-D – Piezometer Data Sheets
- III-E.5-E – TDLR Well Reports
- III-E.5-F – Geotechnical Test Data
- III-E.5-G – Subsurface Water Analytical Testing Results

Attachment III-F - Groundwater Monitoring Plan

1.0	Introduction 330.63(f)	1
2.0	Point of Compliance 330.63(f)(1-3)	2
3.0	Groundwater Monitoring Program 330.63(f)(4)	4
4.0	Groundwater Sampling and Analysis Plan 330.63(f)(5)	7
5.0	Groundwater Monitoring System Certification 330.403(e)	8

Attachment III-F Appendix III-F.1 – Figures

III-F.1-1 Groundwater Monitoring System Plan	1
III-F.1-2 Typical Groundwater Monitoring Well Detail	2

Attachment III-F Appendix III-F.2 – Groundwater Sampling and Analysis Plan

1.0	INTRODUCTION.....	1
2.0	GROUNDWATER SAMPLING PROCEDURES	2
2.1	Field Setup.....	2
2.2	Well Integrity.....	2

Master Table of Contents - continued

2.3	Depth to Water Measurements	3
2.4	Monitor Well Purging.....	3
2.4.1	Purging Three Well Volumes.....	4
2.4.2	Low-Flow Purging.....	5
2.5	Sample Collection	6
2.6	Sample Containers and Labeling.....	7
2.7	Sample Preservation and Shipment	8
2.8	Quality Assurance and Quality Control.....	9
2.9	Chain-of-Custody Documentation.....	9
2.10	Equipment Decontamination	10
2.11	Field Documentation	11
3.0	LABORATORY QUALITY ASSURANCE AND QUALITY CONTROL	13
4.0	GROUNDWATER MONITORING REQUIREMENTS	16
4.1	Detection Monitoring	16
4.1.1	Detection Monitoring Parameters.....	16
4.1.2	Detection Monitoring Frequency	18
4.1.3	Detection Monitoring Statistical Methods.....	18
4.1.4	Detection Monitoring Reporting and Submittals.....	20
4.2	Assessment Monitoring	22
4.2.1	Assessment Monitoring Parameters	23
4.2.2	Assessment Monitoring Frequency	23
4.2.3	Assessment Monitoring Statistical Methods	24
4.2.4	Assessment Monitoring Reporting and Submittals	25
4.2.5	Assessment of Corrective Measures and Remedy.....	26
5.0	GROUNDWATER MONITORING SYSTEM	28

Attachment III-F, Appendix III-F.2 – List of Tables

Table III-F.2-0	– Laboratory Precision and Accuracy Criteria	17
Table III-F.2-1	- Typical Sampling, Preservation, and Storage Procedures for Groundwater Monitoring Constituents.....	28
Table III-F.2-2	- Required Detection Monitoring Constituents.....	30
Table III-F.2-3	- Optional Groundwater Quality Indicator Parameters.....	32

Attachment III-F, Appendix III-F.2-1

Laboratory Review Check List

Attachment III-G - Landfill Gas Management Plan

1.0	INTRODUCTION §330.371(a)	1
2.0	METHANE MONITORING PROGRAM - §330.371(b)	3
2.1	Site Conditions	3
2.2	Accommodations for Pipelines.....	4
2.3	Monitoring Frequency	4
3.0	ACTION PLAN - §330.371(c-d)	5
3.1	Immediate Actions to Protect Human Health.....	5
3.2	Verification Procedures	7

Master Table of Contents - continued

3.3	Action to Be Taken within Seven Days.....	8
3.4	Action within 60 Days.....	9
3.5	Alternative Schedules for Demonstrating Compliance	9
4.0	LANDFILL GAS PROGRAM IMPLEMENTATION - §330.371(e)-(f)	10
5.0	LANDFILL GAS MANAGEMENT PLAN - §330.371(g)	11
5.1	General	11
5.2	Landfill Gas Collection and Control System.....	11
5.3	Landfill Gas Wells.....	12
5.4	Landfill Gas Header System.....	13
5.5	Landfill Gas Flare.....	13
5.6	Landfill Gas System Maintenance.....	14
5.7	Backup Plan.....	14
6.0	Perimeter and Continuous Monitoring Network - §330.371(h-i).....	16
6.1	Perimeter Monitoring	16
6.2	Gas Monitoring Probe Placement.....	16
6.3	Gas Monitoring Probe Construction.....	17
6.4	Inspection and Maintenance	18
6.5	Monitoring Equipment	18
6.6	Gas Monitoring Probe Sampling Procedures	19
6.7	Building/Structure Monitoring	20
6.8	Utility Trench Vent Monitoring	21
7.0	RECORD KEEPING AND REPORTING.....	22

Attachment III-G, Appendix III-G.1 - Figures

III-G.1-1	Landfill Gas Monitoring Plan	1
III-G.1-2	Typical Gas Probe and Utility Vent.....	2

Attachment III-H - Closure Plan

1.0	CLOSURE PLAN	1
1.1	General	1
1.2	Estimate of Maximum Inventory of Waste on Site.....	1
1.3	Estimate of Largest Area Requiring Final Cover	2
2.0	LANDFILL FINAL COVER SYSTEM	4
2.1	Landfill Final Cover System Design	4
2.2	Installation Methods and Procedures.....	4
2.3	Construction Procedures.....	4
3.0	CLOSURE PROCEDURES.....	6
3.1	Landfill Final Cover/Closure Sequence	6
3.2	Landfill Closure During Active Life	6
3.3	Liquid Waste Solidification Unit Closure	7
3.4	Citizens Convenience Center Closure	8
3.5	Leachate and Contaminated Water Storage.....	8
4.0	CLOSURE SCHEDULE.....	9
4.1	Final Cover Construction	9
4.2.1	Closure Plan Implementation	9

Master Table of Contents - continued

4.3 Provisions for Extending Closure Period 11
 5.0 CLOSURE COST ESTIMATE.....12

Attachment III-I - Post-Closure Care Plan

1.0 REGULATIONS1
 2.0 POST-CLOSURE ACTIVITIES.....2
 2.1 Introduction2
 2.2 Monitoring and Maintenance.....2
 2.3 Decreasing Post-Closure Period3
 2.4 Increasing Post-Closure Period4
 2.5 Completion of Post-Closure Period.....4
 3.0 PERSON RESPONSIBLE FOR CONDUCTING POST-CLOSURE ACTIVITIES5
 4.0 POST-CLOSURE LAND USE6
 4.1 Intended Use.....6
 4.2 Constraints on Post-Closure Construction.....6
 5.0 POST-CLOSURE CARE COST ESTIMATE7

Attachment III-J - Cost Estimates for Closure and Post-Closure Care

1.0 INTRODUCTION..... 1
 2.0 Closure and Post-Closure Care Costs.....3
 2.1 Closure Costs.....3
 2.2 Post-Closure Costs.....3
 3.0 Closure and Post-closure Care Cost Estimates.....5
 4.0 Financial Assurance and Cost Estimate Adjustments6
 4.1 Financial Assurance.....6
 4.2 Cost Estimate Revisions6

Attachment III-J, APPENDIX III-J.1

Closure and Post-Closure Care Cost Estimates

PART IV

1.0	INTRODUCTION §330.121	1
1.1	Waste Processing and Disposal Units	1
1.2	Facility Location and Access.....	2
1.3	Waste Delivery	2
1.4	TPDES Permitting.....	3
1.5	Pre-Operation Notice §330.123	3
2.0	RECORDKEEPING AND REPORTING §330.125	4
2.1	Required Notifications.....	6
2.2	Record Retention Period.....	7
2.3	Signatories	7
2.4	Other Records and Reporting	7
3.0	WASTE ACCEPTANCE RATE.....	8
3.1	Requirements.....	8
4.0	PERSONNEL §330.127	10
4.1	Operating Procedures §330.127	13
4.2	Training	14
5.0	EQUIPMENT §330.127(2)	16
6.0	DETECTION AND PREVENTION OF DISPOSAL OF PROHIBITED WASTES §330.127(5).....	18
6.1	Training [330.127(5)(C)].....	19
6.2	Notification of Load Refusal [330.127(5)(D)]	20
6.3	Remediation [330.127(5)(E)]	20
7.0	SAFETY	22
7.1	Enforcement of Site Rules.....	22
8.0	FIRE PROTECTION §330.129 and 330.221	23
8.1	Equipment and Planning.....	23
8.2	Training	24
8.3	Fire Prevention and Control	24
8.4	Fires in Municipal Solid Waste	25
8.5	Fires at Citizen Convenience Center	27
8.6	Notifications	27
9.0	ACCESS CONTROL §330.131 and 330.223	28
10.0	UNLOADING OF WASTE §330.133 and §330.225.....	29
10.1	Grading, Placement, and Compaction of Waste.....	29
10.2	Special Requirements for Industrial Waste	30
11.0	OPERATING HOURS, SIGNS, AND NOTICES §330.135, 330.137, 330.229 and 330.231	31
11.1	Hours of Operation.....	31
11.2	Entrance Sign.....	31
11.3	Directional Signs	31
11.4	Information Notices.....	31

Master Table of Contents - continued

12.0	CONTROL OF WINDBLOWN WASTE AND LITTER §330.139 and 330.233	32
13.0	EASEMENTS AND BUFFER ZONES §330.141 & §330.543	33
13.1	Easements	33
13.2	Buffer Zones	33
14.0	LANDFILL MARKERS AND BENCHMARK §330.143	34
15.0	MATERIALS ALONG THE ROUTE TO THE SITE §330.145 and 330.235	36
16.0	DISPOSAL OF LARGE ITEMS §330.147.....	37
17.0	AIR CRITERIA §330.149.....	38
17.1	Dust Control	38
17.2	Landfill Gas Control.....	38
17.3	Odor Management	38
18.0	DISEASE VECTOR CONTROL §330.151	40
19.0	SITE ACCESS ROADS §330.153 and 330.237	41
20.0	SALVAGING AND SCAVENGING §330.155	42
21.0	ENDANGERED SPECIES PROTECTION §330.157	43
22.0	LANDFILL GAS CONTROL §330.159.....	44
23.0	ABANDONED OIL, GAS, AND WATER WELLS §330.161	45
24.0	COMPACTION OF SOLID WASTE §330.163	47
25.0	LANDFILL COVER §330.165	48
25.1	Intermediate Cover	48
25.2	Alternate Daily Cover.....	49
25.3	Final Cover	49
25.4	Erosion of Cover.....	50
25.5	Cover Application Record	50
26.0	PONDED WATER PLAN §330.167	51
27.0	DISPOSAL OF SPECIAL WASTES §330.171.....	52
27.1	Wastes Requiring Prior Approval.....	52
27.2	Waste Not Requiring Prior Approval.....	53
28.0	DISPOSAL OF INDUSTRIAL WASTES §330.173	56
29.0	VISUAL SCREENING OF DEPOSITED WASTE §330.175.....	58
30.0	LEACHATE AND GAS CONDENSATE RECIRCULATION §330.177.....	59
31.0	FACILITY INSTALLATION AND MAINTENANCE §330.179	61
31.1	Facility Maintenance and Inspection §335.585	61
31.2	Personnel Training §335.586.....	62
31.3	Waste Analysis §335.587	62
31.4	Ignitable, Reactive, or Incompatible Wastes §335.588	63
31.5	Contingency Plan §335.589.....	64

Part IV - List of Tables

Table IV-1 Recordkeeping Requirements	4
Table IV-2 Projected Waste Acceptance Annual Rates	8
Table IV-3 Personnel Types, Descriptions and Required Training.....	12
Table IV-4 List of Equipment and Uses for Landfill Operations.....	16
Table IV-5 Waste Acceptance vs. Equipment Numbers	17
Table IV-6 Stockpile Volume for Fire Control	26
Table IV-7 Access Control.....	28
Table IV-8 Landfill Markers	34
Table IV-9 Facility Maintenance and Inspection Schedule.....	61

Part IV, Attachment IV-A
Contingency Plan

Part IV, Attachment IV-B
Liquid Waste Solidification